



# **W-band Assessment Agenda**



- **W-band receiver**
  - **Status (Seiffert)**
  - **Downconverter design (Teitelbaum, Bagri)**
  - **Noise temperature calibration strategy (all)**
- **Blind pointing model development (Richter)**
- **Task plan review (all)**
- **Initial observing campaign (all)**
- **TMO Progress Report status (all)**

## W-band Assessment Downconverter Design




- Accelerate development of phase-stable 75 GHz first stage downconverter by leveraging existing design that has succeeded in VLBI fringe test
  - Fringes were detected at Ka-band between DSS-13 and DSS-25 using RTB2
  - DSS-25 utilizes a 31.7 GHz downconverter that “translates the 31.8 - 32.3 GHz frequency band to the 100-600 MHz band with one fixed local oscillator at 31.7 GHz. The L.O. is a synthesizer with output frequency of 7.925 GHz, phase-locked to an external 100 MHz reference. The synthesizer output is followed by two x2 multipliers to provide the 31.7 GHz L.O.”
  - DSS-25 specifications obtained from Chau Buu to start the design:

"The Ka-band Downconverter at DSS 25 has met the following specifications:

	Specified	Measured
Residual Phase Noise	-63 dBc/Hz at 1 Hz offset	-70 dBc/Hz at 1 Hz offset
	-73 dBc/Hz at 10 Hz	-78 dBc/Hz at 10 Hz
	-83 dBc/Hz at 100 Hz	-86 dBc/Hz at 100 Hz
	-90 dBc/Hz at 1 kHz	-92 dBc/Hz at 1 kHz
Allan Deviation	1.0e-13 at 1 s	2.0e-14 at 1 s
	4.7e-15 at 10 s	2.0e-15 at 10 s
	5.6e-16 at 1000 s	7.0e-17 at 1000 s
	5.5e-16 at 3600 s	7.0e-17 at 1000 s"


## **W-band Assessment Downconverter Design (Cont'd)**



- **Based on considerations of integrated noise power and concerns about inadequate fall-off of the Ka-band design at high offset frequencies, we extended the phase noise specification for the 75 GHz W-band DC as follows:**


<b>Residual Phase Noise</b>	<b>-63 dBc/Hz at 1 Hz offset</b>
	<b>-73 dBc/Hz at 10 Hz</b>
	<b>-83 dBc/Hz at 100 Hz</b>
	<b>-90 dBc/Hz at 1 kHz</b>
	<b>-100 dBc/Hz at 10 kHz</b>
	<b>-110 dBc/Hz at 100 kHz</b>
	<b>-120 dBc/Hz at 1 MHz offset and beyond</b>

- **Technical requirements have been communicated to Conrad Foster and MTC to cost the job**
  - If affordable, consider building two
- **Alternative approach is to generate 18.75 GHz with DSS-13 resident Wiltron synthesizer, locked to station 100 MHz, then x4 multiply**
  - Planning to bring Wiltron to JPL for phase noise measurement at Section 335 FTS lab



# W-band Assessment

## Downconverter Design (Cont'd)

**JPL**


- $F_{\text{SKY}} \pm \text{BW} = 90 \pm 6 \text{ GHz}$ 
  - VLBI at 86 GHz with 500 MHz instantaneous bandwidth
  - 3 mm spectroscopy, tunable over 12 GHz
- Downconverter frequency = **75 GHz**
  - VLBI and 3mm within tuning range of YIG filter, MMS
  - Can existing Ka-band design be applied with **18.75 GHz** synthesizer in place of 7.925 GHz, with similar phase noise characteristics? Good enough?

Existing Equipment


YIG Tuning Range: 8 - 26.5 GHz

YIG can be bypassed

MMS Tuning Range: 1 - 26.5 GHz

- Downconverter technical issues raised
  - ~18 GHz synthesizer falls in heart of tuning range of second LO stage (MMS, YIG)
  - Is YIG filter phase stability a problem for VLBI


## **W-band Assessment Strawman Task Plan**



- **Complete the phase stabilization of the W-band receiver (Q2)**
  - **Complete the development of computer-controlled noise temperature calibration instrumentation (Q2)**
  - **Develop blind-pointing capability for W-band (Q3)**
  - **Measure the antenna aperture efficiency (Q3)**
- 

- **Obtain first fringes (Q3)**
- **Apply raster scan technique at W-band (Q3)**
- **Obtain data for antenna servo system study (Q3)**
- **Complete W-band link margin study (Q3)**
- **Explore implementation options to improve efficiency (Q4)**
- **Develop detectable point source catalog (Q4)**

## **W-band Assessment Initial Observing Campaign**



- **Cultivate an observing team**
  - Seiffert, Bagri, Teitelbaum, Jones, Kuiper, ...
- **Initial DSS-13 commitment - one prime shift pass per week**
  - After Mike S “blesses” the receiver
  - Usage to be coordinated by observing team
- **Additional observing time can be requested by anyone**
  - Requestor is responsible for observation